

PHASE 1 BID PROPOSAL

Grove Way/Bush Street Realignment					
ITEM NO.	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	EXTENSION
ROADWAY					
150-1000	TRAFFIC CONTROL	LS	1		
153-1300	FIELD ENGINEERS OFFICE TP 3	EA	1		
202-2100	CLEARING (TREE REMOVAL)	LS	1		
210-0100	GRADING COMPLETE	LS	1		
310-1101	GR AGGR BASE CRS, INCL MATL	TN	1365		
402-3100	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE I, GP 1 OR BLEND 1, INCL BITUM MATL & H	TN	242		
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	323		
413-1000	BITUM TACK COAT	GL	180		
441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	193		
441-0018	DRIVEWAY CONCRETE, 8 IN TK	SY	171		
441-0104	CONC SIDEWALK, 4 IN	SY	486		
441-6216	CONC CURB & GUTTER, 8 IN X 24 IN, TP 2	LF	2551		
	ADA SIDEWALK RAMP, TYPE D WITH DETECTABLE WARNING SURFACE	EA	6		
	ADA SIDEWALK RAMP, TYPE C WITH DETECTABLE WARNING SURFACE	EA	1		
	ADA SIDEWALK RAMP, TYPE B WITH DETECTABLE WARNING SURFACE	EA	1		
	CONCRETE STAIRS	LS	1		
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	424		
610-1700	REM SAN SEWER PIPE	LF	446		
610-2586	REM ASPH PVMT INCL BASE	SY	3056		
610-2845	REM CONC SIDEWALK	SY	169		
610-2845	REM CONC PVMT	SY	437		
610-5791	REMOVE CHAIN FENCE	LF	246		
610-6515	REM HIGHWAY SIGN, STD	EA	6		
611-3000	RECONSTR CATCH BASIN, GROUP 1	EA	1		
	REMOVAL AND STORAGE OF CDA SIGN, DEMOLITION OF EXISTING SIGN FOOTING	LS	1		
	REMOVAL AND TEMPORARY RESETTING OF MAILBOXES	EA	4		
	DEMOLITION AND DISPOSAL OF ALL OTHER ITEMS	LS	1		
	PERMANENTLY RESET MAILBOXES	EA	4		
	PERMANENTLY RESET CDA SIGN, INCLUDING FOOTING DESIGN AND SIGN PERMIT	LS	1		
611-8050	ADJUST MANHOLE TO GRADE	EA	2		
660-0008	SAN SEWER PIPE, 8 IN, PVC	LF	306		
660-2043	SEWER LATERAL, 6 IN	LF	160		
660-2600	SEWER CLEANOUTS	EA	4		
668-1100	CATCH BASIN, GP 1	EA	2		
668-1110	CATCH BASIN, GP 1, ADDL DEPTH	LF	4		
668-2100	DROP INLET, GP 1	EA	5		
668-2110	DROP INLET, GP 1, ADDL DEPTH	LF	8		
	18" PRECAST HEADWALL	EA	2		
	COORDINATION WITH UTILITY PROVIDERS	LS	1		
668-3300	SAN SEWER MANHOLE, TP 1	EA	3		
668-3311	SAN SEWER MANHOLE, TP 1, ADDL DEPTH, CL 1	LF	10		
643-1151	CH LK FENCE, ZC COAT, 6 FT, 6 GA	LF	122		
RETAINING WALL A					
	WALL A PERMIT	EA	1		
515-2015	GALV STEEL PIPE HANDRAIL - WALL A (BLACK POWDER COATED)	LF	100		
	WALL A COMPLETE	LS	1		
RETAINING WALL B					
	WALL B DESIGN AND PERMIT	EA	1		
515-2015	GALV STEEL PIPE HANDRAIL - WALL B (BLACK POWDER COATED)	LF	245		
630-0010	SEGMENTAL CONCRETE FACING UNITS	SF	915		
630-0300	MODULAR BLOCK RETAINING WALL CONCRETE LEVELING PAD	LF	249		
630-0600	MODULAR BLOCK RETAINING WALL PRECAST COPING	LF	245		
	WALL B MISC. ITEMS (BACKFILL, GEGRID (IF REQUIRED), ETC.)	LS	1		
	RETAINING WALL G COMPLETE, INCLUDING DESIGN	SF	112		
	RETAINING WALL H COMPLETE, INCLUDING DESIGN	SF	42		

PHASE 1 BID PROPOSAL

Grove Way/Bush Street Realignment					
ITEM NO.	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	EXTENSION
SIGNING & MARKING					
636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	3		
636-1036	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11	SF	15		
	STREET SIGNS	EA	2		
636-2090	GALV STEEL POSTS, TP 9	LF	4		
652-5451	SOLID TRAFFIC STRIPE, 5 IN, WHITE (PARKING)	LF	230		
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	1680		
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	30		
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	385		
656-0050	REMOVE EXIST SOLID TRAF STRIPE, 5 IN, THERMOPLASTIC	LF	255		
	ADA SIGNAGE, SYMBOL, AND WHEELSTOP	LS	1		
PERMANENT EROSION CONTROL					
700-6910	PERMANENT GRASSING	AC	0.75		
700-7000	AGRICULTURAL LIME	TN	1		
700-8000	FERTILIZER MIXED GRADE	TN	1		
700-8100	FERTILIZER NITROGEN CONTENT	LB	60		
603-2012	STN DUMPED RIP RAP, TP 1, 12 IN	SY	60		
603-2997	FILTER BLANKET	SY	60		
716-2000	EROSION CONTROL MATS, SLOPES	SY	350		
TEMPORARY EROSION CONTROL					
163-0232	TEMPORARY GRASSING	AC	1		
163-0240	MULCH	TN	3		
163-0300	CONSTRUCTION EXIT	EA	3		
163-0527	CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS	EA	12		
	CONSTRUCT AND REMOVE DIVERSION CHANNEL	LS	1		
	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT TRAP WITH ROCK OUTLET	EA	1		
	CONSTRUCT AND REMOVE DOWNDRAIN WITH OUTLET PROTECTION	EA	1		
	CONSTRUCT AND REMOVE TEMPORARY CULVERT (18" CMP)	EA	1		
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	8		
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	1590		
165-0041	MAINTENANCE OF CHECK DAMS - ALL TYPES	LF	12		
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	3		
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	8		
167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	1		
167-1500	WATER QUALITY INSPECTIONS	MO	12		
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	1590		
	TREE PROTECTION FENCING	LF	810		

PHASE 1 BID PROPOSAL

Grove Way/Bush Street Realignment					
ITEM NO.	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	EXTENSION
LIGHTING					
615-1200	DIRECTIONAL BORE - 2 IN	LF	60		
	POLE FOUNDATION	EA	5		
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	365		
682-9022	ELECTRICAL JUNCTION BOX, REINFORCED PLASTIC MORTAR	EA	3		
STREETSCAPE					
702-0170	CLEYERA JAPONICA- 'Contherann P.P.11737'	EA	6		
702-0470	ILEX VOMITORIA NANA	EA	17		
702-0700	NYSSA SYLVATICA	EA	1		
	Ilex 'Conaf' - Oak Leaf Red Holly	EA	1		
702-9025	LANDSCAPE MULCH	SY	50		
WATER MAIN RELOCATION					
	6 IN DUCTILE IRON PIPE	LF	120		
	8 IN DUCTILE IRON PIPE	LF	925		
	2 IN COPPER PIPE	LF	50		
	2 IN GALVNZIED STEEL PIPE	LF	50		
	DUCTILE IRON FITTINGS	LBS	1500		
	6 IN RESTRAINED JOINT GASKET	EA	4		
	8 IN RESTRAINED JOINT GASKET	EA	45		
	6 IN RESTRAINED JOINT GLAND	EA	25		
	8 IN RESTRAINED JOINT GLAND	EA	45		
	6 IN LINE STOP	EA	1		
	WET TAP	EA	3		
	6 IN GATE VALVE ASSEMBLY	EA	8		
	8 IN GATE VALVE ASSEMBLY	EA	9		
	CONCRETE VALVE MARKER	EA	6		
	ABANDON EXISTING VALVE - IN PAVEMENT	EA	3		
	CONNECT EXISTING SERVICE - SHORT SIDE	EA	1		
	CONNECT EXISTING SERVICE - LONG SIDE	EA	4		
	CONCRETE THRUST BLOCK	CY	15		
	6 IN WATER METER VAULT	EA	1		
	6 IN BACKFLOW PREVENTER	EA	1		
	FIRE DEPARTMENT CONNECTION	EA	1		
	FIRE HYDRANT ASSEMBLY	EA	4		
			PHASE 1 CONSTRUCTION TOTAL		

PHASE 2 BID PROPOSAL

CDA SITE IMPROVEMENTS					
ITEM NO.	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	EXTENSION
	ENTIRE PHASE 2 PROJECT AS SHOWN ON CONSTRUCTION DOCUMENTS	LS	1		
			PHASE 2 CONSTRUCTION TOTAL		



A small table with three columns and three rows, all cells are empty, located in the center of the page.