

# Bid Schedule

PRIMARY PROJECT					
ITEM	DESCRIPTION	UNITS	QUANTITY	PRICE	AMOUNT
150-1000	TRAFFIC CONTROL - HPP00-0000-00(265)	LS	1		
163-0232	TEMPORARY GRASSING	AC	6		
163-0240	MULCH	TN	200		
163-0300	CONSTRUCTION EXIT	EA	5		
163-0502	CONSTR AND REMOVE SILT CONTROL GATE,TP 2	EA	5		
163-0503	CONSTR AND REMOVE SILT CONTROL GATE,TP 3	EA	43		
163-0527	CNST/REM RIP RAP CKDM,STN P RIPRAP/SN BG	EA	128		
163-0529	CNST/REM TEMP SED BAR/ BALED STRAW CD	EA	156		
163-0550	CONS & REM INLET SEDIMENT TRAP	EA	67		
165-0010	MAINT OF TEMP SILT FENCE, TP A	LF	5984		
165-0030	MAINT OF TEMP SILT FENCE, TP C	LF	714		
165-0041	MAINT OF CHECK DAMS - ALL TYPES	LF	2840		
165-0086	MAINT OF SILT CONTROL GATE, TP 2	EA	5		
165-0087	MAINT OF SILT CONTROL GATE, TP 3	EA	43		
165-0101	MAINT OF CONST EXIT	EA	5		
165-0105	MAINT OF INLET SEDIMENT TRAP	EA	67		
167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	4		
167-1500	WATER QUALITY INSPECTIONS	MO	18		
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	11967		
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	1427		
210-0100	GRADING COMPLETE - HPP00-0000-00(265)	LS	1		
310-1101	GR AGGR BASE CRS, INCL MATL	TN	9940		
318-3000	AGGR SURF CRS	TN	40		
402-1812	RECYL AC LEVELING,INC BM&HL	TN	4435		
402-3103	REC AC 9.5 MM SP,TPII,GP2, INCL BM & HL	TN	330		
402-3121	RECYL AC 25MM SP,GP1/2,BM&HL	TN	1942		
402-3130	RECYL AC 12.5MM SP,GP2,BM&HL	TN	4586		
402-3190	RECYL AC 19 MM SP,GP 1 OR 2 ,INC BM & HL	TN	1664		
413-0750	TACK COAT	GL	2552		
432-5010	MILL ASPH CONC PVMT,VARB DEPTH	SY	5548		
441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	901		
441-0104	CONC SIDEWALK, 4 IN	SY	4549		
441-0108	CONC SIDEWALK, 8 IN	SY	421		
441-0301	CONC SPILLWAY, TP 3	EA	1		
441-0600	CONC HEADWALLS	CY	2		
441-0740	CONC MEDIAN, 4 IN	SY	61		
441-0748	CONC MEDIAN, 6 IN	SY	579		
441-5008	CONC HEADER CURB, 6 IN, TP 7	LF	213		
441-5025	CONC HEADER CURB, 4, TP 9	LF	293		
441-6012	CONC CURB & GUTTER/ 6X24TP2	LF	4630		
441-9500	CONC TRAIL PAVE,STD FSH, 6"	SY	973		
446-1100	PVMT REF FAB STRIPS, TP2,18 INCH WIDTH	LF	7977		
500-3101	CLASS A CONCRETE	CY	109		
500-3200	CL A CONC, INCL REINF STEEL	CY	3		
500-9999	CL B CONC,BASE OR PVMT WIDEN	CY	364		

# Bid Schedule

Hardscrabble Road  
PI 0000265

515-2020	GALV STEEL PIPE HDRAIL,2,ROUD	LF	428		
550-1180	STM DR PIPE 18,H 1-10	LF	6152		
550-1240	STM DR PIPE 24,H 1-10	LF	227		
550-1300	STM DR PIPE 30,H 1-10	LF	529		
550-1301	STM DR PIPE 30,H 10-15	LF	15		
550-2180	SIDE DR PIPE 18,H 1-10	LF	259		
550-3618	SAFETY END SECTION 18,SD,6:1	EA	3		
550-4218	FLARED END SECT 18 IN, ST DR	EA	17		
550-4224	FLARED END SECT 24 IN, ST DR	EA	2		
550-4230	FLARED END SECT 30 IN, ST DR	EA	3		
573-2006	UNDDR PIPE INCL DRAIN AGGR 6	LF	500		
600-0001	FLOWABLE FILL	CY	100		
603-2024	STN DUMPED RIP RAP, TP 1, 24	SY	68		
603-7000	PLASTIC FILTER FABRIC	SY	68		
607-1000	MORTAR RUBBLE MASONRY	CY	230		
608-1000	BRICK MASONRY	CY	32		
610-6512	REM HEADWALL - BRICK	EA	1		
610-6512	REM HEADWALL - WOOD	EA	1		
610-6512	REM HEADWALL - CINDER BLOCK	EA	1		
610-6512	REM HEADWALL - CONCRETE	EA	1		
611-8040	ADJUST DROP INLET TO GRADE	EA	1		
611-8050	ADJUST MANHOLE TO GRADE	EA	1		
615-1100	DIRECTIONAL BORE PIPE - 5 IN	LF	280		
621-4022	CONCRETE SIDE BARRIER, TY 2B	LF	50		
621-4023	CONCRETE SIDE BARRIER, TY 2C	LF	250		
632-0003	CHANGEABLE MESS SIGN,PORT,TP 3	EA	3		
634-1200	RIGHT OF WAY MARKERS	EA	68		
636-1033	HWY SIGNS, TP1MAT,REFL SH TP 9	SF	259		
636-1036	HWY SGN,TP1MAT,REFL SH TP 11	SF	391		
636-2070	GALV STEEL POSTS, TP 7	LF	851		
636-2080	GALV STEEL POSTS, TP 8	LF	58		
636-2090	GALV STEEL POSTS, TP 9	LF	286		
639-1235	TREATED TIMBER POLE, CL 2, 35'	EA	4		
641-1100	GUARDRAIL, TP T	LF	42		
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	1		
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	1		
643-0050	TEMPORARY FIELD FENCE	LF	300		
643-8200	BARRIER FENCE (ORANGE), 4 FT	LF	1380		
647-0220	TRAF SIGNAL INSTALLATION, TEMP	LS	1		
647-6200	LOOP DETECTOR, 6 FT X 6 FT, BIPOLE	EA	6		
652-0094	PVMT MARKING, SYMBOL, TP 4	EA	34		
652-5452	SOLID TRAF STRIPE, 5 IN, YELLO	LF	204		
653-0110	THERM PVMT MARK, ARROW, TP 1	EA	3		
653-0120	THERM PVMT MARK, ARROW, TP 2	EA	25		
653-0130	THERM PVMT MARK, ARROW, TP 3	EA	4		
653-0150	THERM PVMT MARK, ARROW, TP 5	EA	1		
653-1501	THERMO SOLID TRAF ST 5 IN, WHI	LF	28757		

# Bid Schedule

Hardscrabble Road  
PI 0000265

653-1502	THERMO SOLID TRAF ST, 5 IN YEL	LF	11139		
653-1704	THERM SOLID TRAF STRIPE,24,WH	LF	272		
653-1804	THERM SOLID TRAF STRIPE, 8,WH	LF	3978		
653-3501	THERMO SKIP TRAF ST, 5 IN, WHI	GLF	3327		
653-4830	THER SKIP TRAF ST, 18 IN, WHT	GLF	112		
653-6004	THERM TRAF STRIPING, WHITE	SY	117		
653-6006	THERM TRAF STRIPING, YELLOW	SY	1484		
654-1001	RAISED PVMT MARKERS TP 1	EA	299		
654-1003	RAISED PVMT MARKERS TP 3	EA	61		
654-1010	RAISED PVMT MARKERS TP 10	EA	5		
668-1100	CATCH BASIN, GP 1	EA	6		
668-1110	CATCH BASIN, GP 1, ADDL DEPTH	LF	2		
668-2100	DROP INLET, GP 1	EA	56		
668-2110	DROP INLET, GP 1, ADDL DEPTH	LF	18		
668-4300	STORM SEW MANHOLE, TP 1	EA	8		
668-4311	ST SEW MANHOLE,TP 1,A DEP,CL 1	LF	12		
681-1150	LT STD, ALUM,14'MH,POST TOP	EA	4		
681-4300	LT STD, 30' MH, 6' ARM	EA	10		
681-6320	LUMINAIRE,TP 2, 150W,HP SODIUM	EA	4		
681-6346	LUMINAIRE,TP 3, 250W,HP SODIUM	EA	10		
682-1404	CABLE, TP XHHW, AWG NO 10	LF	8800		
682-1405	CABLE, TP XHHW, AWG NO 8	LF	4000		
682-6110	CONDUIT, RIGID, 1 IN	LF	110		
682-6219	CONDUIT, NONMETL, TP 2, 1 IN	LF	3700		
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	90		
682-6225	CONDUIT, NONMETL, TP 2, 1 1/2	LF	50		
682-6233	CONDUIT, NONMETL, TP 3, 2 IN	LF	180		
682-6233	CONDUIT, NONMETL, TP 3, 2 IN	LF	100		
682-9000	MAIN SVC PICK UP POINT	LS	1		
682-9022	ELEC JCT BX,REF PLASTIC MORTAR	EA	3		
682-9950	DIRECTIONAL BORE - 2 IN	LF	840		
700-6910	PERMANENT GRASSING	AC	8		
700-7000	AGRICULTURAL LIME	TN	49		
700-8000	FERTILIZER MIXED GRADE	TN	2		
700-8100	FERTILIZER NITROGEN CONTENT	LB	399		
700-9300	SOD	SY	15997		
702-0212	CRATAEGUS VIRIDIS - 3 Inch Caliper	EA	3		
702-0470	ILEX VOMITORIA Nana - 3 Gal	EA	129		
702-9005	SPRING APPLICATION FERTILIZER	LB	109		
702-9025	LANDSCAPE MULCH	SY	200		
716-2000	EROSION CONTROL MATS, SLOPES	SY	275		
999-3800	RECTANGULAR RAPID BEACON ASSY	EA	2		
999-3900	TESTING - RAPID RECTANGULAR BEACON ASSEMBLY	LS	1		
<b>PRIMARY PROJECT TOTAL:</b>					
<b>Bid Amount in Words:</b>					

# Bid Schedule

**Hardscrabble Road  
PI 0000265**

<b>WATER DISTRIBUTION</b>					
ITEM	DESCRIPTION	UNITS	QUANTITY	PRICE	AMOUNT
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	7000		
500-3101	CLASS A CONCRETE	CY	50		
600-0001	FLOWABLE FILL	CY	100		
611-8050	ADJUST MANHOLE TO GRADE	EA	1		
611-8120	ADJUST WATER METER BOX TO GRADE	EA	10		
611-8140	ADJUST WATER VALVE BOX TO GRADE	EA	10		
670-1060	WATER MAIN, 6 IN	LF	300		
670-1080	WATER MAIN, 8 IN	LF	200		
670-1100	WATER MAIN, 10 IN	LF	7000		
670-1500	CAP OR REMOVE EXISTING WATER MAIN	EA	4		
670-2002	VALVE MARKER	EA	75		
670-2060	GATE VALVE, 6 IN	EA	13		
670-2080	GATE VALVE, 8 IN	EA	2		
670-2100	GATE VALVE, 10 IN	EA	17		
670-2500	INSERTION VALVE 8 IN-10 IN	EA	2		
670-3087	TAPPING SLEEVE & VALVE ASSEMBLY, 8 IN X 8 IN	EA	2		
670-3108	TAPPING SLEEVE & VALVE ASSEMBLY, 10 IN X 10 IN	EA	2		
670-3129	TAPPING SLEEVE & VALVE ASSEMBLY, 12 IN X 12 IN	EA	1		
670-4000	FIRE HYDRANT	EA	13		
670-5010	WATER SERVICE LINE, 1 IN	LF	100		
670-5020	WATER SERVICE LINE, 2 IN	LF	100		
670-5620	WATER SERVICE LINE, 3/4 IN	LF	200		
670-7000	STEEL CASING - 18 IN	LF	250		
670-9710	RELOCATE EXIST FIRE HYDRANT	EA	2		
670-9720	RELOCATE EXIST WATER VALVE, INCL BOX	EA	4		
670-9730	RELOCATE EXIST WATER METER, INCL BOX	EA	4		
670-9920	REMOVE EXIST FIRE HYDRANT	EA	1		

**WATER DISTRIBUTION TOTAL:**

**Bid Amount in Words:**

**GRAND TOTAL:**

**Bid Amount in Words:**

**Bidder's Company Name:**

**Key:**

- |                         |                  |
|-------------------------|------------------|
| AC = Acre               | LF = Linear Feet |
| CY = Cubic Yard         | LS = Lump Sum    |
| EA = Each               | SF = Square Feet |
| GL = Gallon             | SY = Square Yard |
| GLF = Gross Linear Feet | TN = Ton         |
| LB = Pound              |                  |