

**City of Roswell
Purchasing Division**

**Michael Fischer
Interim City Administrator**

**Jere Wood
Mayor**

ADDENDUM NUMBER 1

INVITATION TO BID# 17-255-G

ZION CIRCLE PERMEABLE PAVER INSTALLATION

October 16, 2017

To All Prospective Bidders:

1. Changes to Bid Documents

a. General Requirements and Technical Specifications

- i. Section 1.3 CASH ALLOWANCE WORK is changed as follows:
 - 1. Replace throughout Section 1.3, "Item 16" with "Item 17".
- ii. Section 1.04 QUALITY ASSURANCE
 - 1. Delete item 1.04 (B), which requires that the Contractor's Site Foreman hold an ICPI contractor certification. We no longer require this Certification.

b. Price Bid Form – Attachment A – SCHEDULE OF ITEMS is hereby changed as follows:

- i. Replace Price Bid Form – Attachment A – SCHEDULE OF ITEMS with the Revised SCHEDULE OF ITEMS, which is attached to this Addendum.

2. Questions and Answers

#	QUESTION	ANSWER
1.	Please provide clarification on item #16 on the bid form. It states in the General Requirements that Item 16 should be for \$7,500 for additional items, but the bid form has 1,000 sf for Geotextile?	This addendum changes those references to Item 17, and changes Item 17 such that the \$7,500 is now accounted for in the line item.
2.	Please clarify if the liquidated damages accrue during weekends and holidays?	Liquidated damages are on a calendar day basis, including weekends and holidays.

3.	In the Standard General Notes, page 13, item #9, states that the City of Roswell will not be responsible for the failure of any utility company to respond in a timely manner. Will the City of Roswell grant additional time to complete the project for unexpected conflicts with Utilities and/or additional work needed per soil engineers request.	The City will consider requests for time extension due to unseasonable weather and other circumstances beyond the Contractor's reasonable control.
4.	Will the City issue additional compensation for undercutting, rock removal, and/or utility relocation?	Rock is not expected to be encountered and no utility relocations are expected for the project. If one or both of these conditions are encountered the City will work with the selected contractor to establish payment for rock and/or for utility relocation.
5.	Please specify the type/strength of Geogrid required in Item #16 of bid form.	Tensar TriAX TX160 or approved equal.
6.	Will the City allow a bidder to obtain the ICPI Certification after bids are due?	No. However, the ICPI certification requirement has been deleted. The City wants to emphasize that we want contractors with experience in pavers and utilities.

Dates listed in the Bid Cover have not changed.

COMPLETE THIS ADDENDUM, SIGN and SUBMIT with the ITB to:

**City of Roswell – Purchasing Division
Roswell City Hall
38 Hill Street, Suite 130
Roswell, GA 30075**

I hereby acknowledge receipt of Addendum 1 and have incorporated the changes into my proposal response for the above mentioned ITB.

COMPANY NAME: _____ **CONTACT PERSON:** _____

ADDRESS: _____ **CITY:** _____ **STATE:** ____ **ZIP:** ____

PHONE: _____ **FAX:** _____ **EMAIL ADDRESS:** _____

SIGNATURE: _____ **DATE:** _____

PRICE BID FORM - ATTACHMENT A

Revised SCHEDULE OF ITEMS

ITB# 17-255-G

ZION CIRCLE PERMEABLE PAVER INSTALLATION

Item No.	Description	Est. Qty.	Unit	Unit Cost (\$)	Total Cost (\$)
1	Mobilization and Demobilization (includes MOT, survey, construction sign, and construction warranty)	1	LS	--	
2	Orange Barrier Fence	550	LF		
3	Temporary Silt Fence - Type C	300	LF		
4	Inlet ESC Protection	2	EA		
5	Pavement/Curb/Subbase Removal (8-inch depth, in-place volume)	2,000	CF		
6	Excavation and compaction of subgrade (earthwork only - includes excavation, compaction, final grading, disposal of excess)	275	CY		
7	Permeable Pavers and Subsurface Stone (3-1/8-inch concrete paver, aggregate in openings, 2-inch bedding material, 6-inch stone base, 24-inch gravel reservoir, geotextile on sides)	2,900	SF		
8	6-inch PVC Underdrain	180	LF		
9	Geotextile partial stop (barrier) in reservoir stone	1	EA		
10	6-inch Concrete Barrier Curb (with crusher run wrapped with geomembrane, geotextile, and geogrid per detail)	17	LF		
11	Asphalt Street restoration	50	SY		
12	Temporary Seeding and Mulch	0.06	AC		
13	Construction Exit	1.00	EA		
14	Sod Restoration	2,500	SF		
15	Owner Directed Rolled Curb Removal and Replacement	50	LF		
16	Owner Directed Geotextile or Geogrid for Bottom of Reservoir Stone	1,000	SF		
17	Allowance for Additional Items	1	LS	--	\$7,500
TOTAL AMOUNT:					